



| | |
|--|--|
| Qty: 2 Ref: 13-9-RCAO Road Closed Access Only | |
| Qty: 2 Ref: 2702 Start of temporary diversion route | |
| Qty: 2 Ref: 2702 End of temporary diversion route | |
| Qty: 1 Ref: 2702 Start of temporary diversion route | |
| Qty: 4 Ref: 2703 Direction of temporary diversion route from junction ahead | |
| Qty: 3 Ref: 2703 Direction of temporary diversion route from junction ahead | |
| Qty: 8 Ref: 2703 Direction of temporary diversion route from junction ahead | |
| Qty: 2 Ref: 7001 Road works ahead | |
| Qty: 2 Ref: 7010-FP-13-9 Nature of temporary hazard ahead - Road Closed | |
| Qty: 3 Ref: 7010-FP-13-9 Nature of temporary hazard ahead - Road Ahead Closed | |



Go Traffic Management

This drawing has been produced for a specific client & project identified below and is not intended for use by any other person or for any other purpose. © Go Traffic Management

Risks

- Design completed from information provided + google maps desktop risk assessment
- Cone lamps must be used on all road with a speed limit of 40mph or more.

Notes

- All signs as per Chapter 8. Distances between cones to be 9m maximum unless otherwise noted.
- Distances between signs NOT to scale for purpose of clarity.
- All sign placement subject to available safe working space.
- The purpose of the Traffic Management Plan is for it to be used only as a guide and all traffic management equipment should be put out according to the 'Safety at Street Works and Road Works - Code of Practice', L4, Red Book & the 'Traffic Signs Manual Chapter 8', i.e. Yellow Book.
- Signs must be placed in accordance with TSM and the scheme RAMS pack.
- Site conditions may have changed since the design of the drawing any changes which subsequently affect the design need to be reported by the Traffic Management Operative & any changes implemented must comply with Chapter 8.

Key

- Sign position and aspect of vision
- Work Space
- Cones
- Diversion Route 1

ROAD SPEED

CROSS SECTION

ROAD CLOSURE

DO NOT SCALE FROM THIS DRAWING

| | | |
|------|----------|-------------|
| REV. | DATE | DESCRIPTION |
| A | 09/12/25 | AS DRAWN |

GTM
Go Traffic Management

Head Office: Go Traffic Management, Chaddock Lane, Worsley, Manchester, M28 1XW
Tel: 0161 351 5370
www.gtm.co.uk

TRAFFIC MANAGEMENT PLAN

Client: **SEVERN TRENT WATER**

Drawing Number: 1606471.0001

Drawing Title: Church Ln, Stourport-on-Severn DY13 0RL

| | | |
|-------------------|--------------------|------|
| Design: | Technical Officer: | REV: |
| Name: M. Gardiner | SC | |
| Signature: | | A |
| Date: 09/12/25 | 09/12/25 | |